

DATASHEET 13

AC/DC CONTROLLER INTEGRATED

VC-3AC/DCP6-125-200-1500-A

REFER TO PAGE 4, LINE NUMBER 8 AC/DC INTEGRATED SOLAR BOREHOLE PUMP PLASTIC IMPELLER



- H AC/DC HYBRID COMPLEMENTARY CONTROLLER
- AC/DC AUTOMATIC SWITCHING CONTROLLER
 M MANUAL CONTROLLER



SAFE AND RELIABLE

SIMPLE INSTALLATION

LARGE FLOW

SPEED~4000r/min 165-145-125 HEAD(m) TOTAL FLOW(m³/h)

HYDRAULIC PERFORMANCE CURVES

Solar Panels Suggestion (≥1.3* PUMP POWER)

TECHNICAL DATA

MODEL	Pu Volt (A	age	Pump Voltage (DC)	Max. Flow (m ³ /h)		Max. Head (m)	Outlet (in)	Power (w)	Min Quantity (pcs)	Series Connection
1 VC - 3AC/DCP6-125-200-1500-A	A 85-2	80V	300 - 800V	6m∛	h	125m	1.25"	1500W	5	
Running Voltages	Running Voltages DC 17		430 V	AC	220	V	AC/DC SINGLE PHASE			



DATASHEET 13

ALL COPPER MOTOR

EXCELLENT QUALITY

DRY RUN SAFEGUARD

DATASHEET 13

Refer to installation guide

Earth Spike **Sold Separately**

Cabtyre Cable Dry run protection. **Sold Separately**



Joint Kit for joining of cables **Sold Separately**

Solar Panels Sold Separately

ENERGY SAVING

SUPER ELEVATION HEAD

NOISE REDUCTION



Combiner Box Sold Separately



Sumbersible Cable **Sold Separately**



Polysteel 3 strand rope **Sold Separately**

